

**Appendix D – TVA Transmission Construction  
Guidelines Near Streams**

Page intentionally blank

## **Tennessee Valley Authority Transmission Construction Guidelines Near Streams**

Even the most carefully designed transmission line project eventually will affect one or more creeks, rivers, or other type of water body. These streams and other water areas are protected by state and federal law, generally support some amount of fishing and recreation, and, occasionally, are homes for important and/or endangered species. These habitats occur in the stream and on strips of land along both sides (the streamside management zone [SMZ]) where disturbance of the water, land, or vegetation could have an adverse effect on the water or stream life. The following guidelines have been prepared to help Tennessee Valley Authority (TVA) Transmission Construction staff and their contractors avoid impacts to streams and stream life as they work in and near SMZs. These guidelines expand on information presented in *A Guide for Environmental Protection and Best Management Practices for Tennessee Valley Authority Construction and Maintenance Activities*.

### **Three Levels of Protection**

During the preconstruction review of a proposed transmission line, TVA Environmental Stewardship and Policy staff will have studied each possible stream impact site and will have identified it as falling into one of three categories: (A) standard stream protection, (B) protection of important permanent streams, or (C) protection of unique habitats. These category designations are based on the variety of species and habitats that exist in the stream as well as state and federal requirements to avoid harming certain species. The category designation for each site will be marked on the plan and profile sheets. Construction crews are required to protect streams and other identified water habitats using the following pertinent set(s) of guidelines:

#### **(A) Standard Stream Protection**

This is the standard (basic) level of protection for streams and the habitats around them. The purpose of the following guidelines is to minimize the amount and length of disturbance to the water bodies without causing adverse impacts on the construction work.

#### **Guidelines:**

1. All construction work around streams will be done using pertinent best management practices (BMPs) such as those described in *A Guide for Environmental Protection and Best Management Practices for Tennessee Valley Authority Construction and Maintenance Activities*, especially Chapter 6, "Standards and Specifications."
2. All equipment crossings of streams must comply with appropriate state permitting requirements. Crossings of all drainage channels, intermittent streams, and permanent streams must be done in ways that avoid erosion problems and long-term changes in water flow. Crossings of any permanent streams must allow for natural movement of fish and other aquatic life.
3. Cutting of trees within SMZs must be accomplished by using either hand-held equipment or other appropriate clearing equipment (e.g., a feller-buncher) that would result in minimal soil disturbance and damage to low-lying vegetation. The

method will be selected based on site-specific conditions and topography to minimize soil disturbance and impacts to the SMZ and surrounding area. Stumps can be cut close to ground level but must not be removed or uprooted.

4. Other vegetation near streams must be disturbed as little as possible during construction. Soil displacement by the actions of plowing, disking, blading, or other tillage or grading equipment will not be allowed in SMZs; however, a minimal amount of soil disturbance may occur as a result of clearing operations. Shorelines that have to be disturbed must be stabilized as soon as feasible.

#### **(B) Protection of Important Permanent Streams**

This category will be used when there is one or more specific reason(s) why a permanent (always-flowing) stream requires protection beyond that provided by standard BMPs. Reasons for requiring this additional protection include the presence of important sports fish (trout, for example) and habitats for federal endangered species. The purpose of the following guidelines is to minimize the disturbance of the banks and water in the flowing stream(s) where this level of protection is required.

##### **Guidelines:**

1. Except as modified by guidelines 2-4 below, all construction work around streams will be done using pertinent BMPs such as those described in *A Guide for Environmental Protection and Best Management Practices for Tennessee Valley Authority Construction and Maintenance Activities*, especially Chapter 6, "Standards and Specifications."
2. All equipment crossings of streams must comply with appropriate state (and, at times, federal) permitting requirements. Crossings of drainage channels and intermittent streams must be done in ways that avoid erosion problems and long-term changes in water flow. Proposed crossings of permanent streams must be discussed in advance with Environmental Stewardship and Policy staff and may require an on-site planning session before any work begins. The purpose of these discussions will be to minimize the number of crossings and their impact on the important resources in the streams.
3. Cutting of trees within SMZs must be accomplished by using either hand-held equipment or other appropriate clearing equipment (e.g., a feller-buncher) that would result in minimal soil disturbance and damage to low-lying vegetation. The method will be selected based on site-specific conditions and topography to minimize soil disturbance and impacts to the SMZ and surrounding area. Cutting of trees near permanent streams must be limited to those required to meet National Electrical Safety Code and danger tree requirements. Stumps can be cut close to ground level but must not be removed or uprooted.
4. Other vegetation near streams must be disturbed as little as possible during construction. Soil displacement by the actions of plowing, disking, blading, or other tillage or grading equipment will not be allowed in SMZs; however, a minimal amount of soil disturbance may occur as a result of clearing operations. Shorelines that have to be disturbed must be stabilized as soon as possible and revegetated as soon as feasible.

**(C) Protection of Unique Habitats**

This category will be used when, for one or more specific reasons, a temporary or permanent aquatic habitat requires special protection. This relatively uncommon level of protection will be appropriate and required when a unique habitat (for example, a particular spring run) or protected species (for example, one that breeds in a wet-weather ditch) is known to occur on or adjacent to the construction corridor. The purpose of the following guidelines is to avoid or minimize any disturbance of the unique aquatic habitat.

**Guidelines:**

1. Except as modified by Guidelines 2-4 below, all construction work around the unique habitat will be done using pertinent BMPs such as those described in *A Guide for Environmental Protection and Best Management Practices for Tennessee Valley Authority Construction and Maintenance Activities*, especially Chapter 6, "Standards and Specifications."
2. All construction activity in and within 30 meters (100 feet) of the unique habitat must be approved in advance by Environmental Stewardship and Policy staff, preferably as a result of an on-site planning session. The purpose of this review and approval will be to minimize impacts on the unique habitat. All crossings of streams also must comply with appropriate state (and, at times, federal) permitting requirements.
3. Cutting of trees within 30 meters (100 feet) of the unique habitat must be discussed in advance with Environmental Stewardship and Policy staff, preferably during the on-site planning session. Cutting of trees near the unique habitat must be kept to an absolute minimum. Stumps must not be removed, uprooted, or cut shorter than 0.30 meter (1 foot) above the ground line.
4. Other vegetation near the unique habitat must be disturbed as little as possible during construction. The soil must not be disturbed by plowing, disking, blading, or grading. Areas that have to be disturbed must be stabilized as soon as possible and revegetated as soon as feasible, in some cases with specific kinds of native plants. These and other vegetative requirements will be coordinated with Environmental Stewardship and Policy staff.

**Additional Help**

If you have questions about the purpose or application of these guidelines, please contact your supervisor or the environmental coordinator in the local Transmission Service Center.

Revision April 2007