Appendix B – U.S. Army Corps of Engineers' Nationwide Permits #13 and #36 and Tennessee Department of Environment and Conservation General Permits: General National Pollutant Discharge Elimination System (NPDES) Permit, General Permit for Bank Stabilization, and General Permit for Construction of Launching Ramps and Public Access Structures

Page intentionally blank

US Army Corps of Engineers®
Nashville District

Nationwide Permit

No. 13 Bank Stabilization

Bank stabilization activities necessary for erosion prevention, provided the activity meets all of the following criteria:

(a) No material is placed in excess of the minimum needed for erosion protection;

(b) The activity is no more than 500 feet in length along the bank, unless this criterion is waived in writing by the district engineer;

(c) The activity will not exceed an average of one cubic yard per running foot placed along the bank below the plane of the ordinary high water mark or the high tide line, unless this criterion is waived in writing by the district engineer;

(d) The activity does not involve discharges of dredged or fill material into special aquatic sites, unless this criterion is waived in writing by the district engineer;

(e) No material is of the type, or is placed in any location, or in any manner, to impair surface water flow into or out of any water of the United States;

(f) No material is placed in a manner that will be eroded by normal or expected high flows (properly anchored trees and treetops may be used in low energy areas); and,

(g) The activity is not a stream channelization activity.

Notification: The permittee must submit a pre-construction notification to the district engineer prior to commencing the activity if the bank stabilization activity: (1) involves discharges into special aquatic sites; (2) is in excess of 500 feet in length; or (3) will involve the discharge of greater than an average of one cubic yard per running foot along the bank below the plane of the ordinary high water mark or the high tide line. (Sections 10 and 404)

US Army Corps
of Engineers ®
Nashville District

Nationwide Permit

No. 36, Boat Ramps

Activities required for the construction of boat ramps, provided the activity meets all of the following criteria:

(a) The discharge into waters of the United States does not exceed 50 cubic yards of concrete, rock, crushed stone or gravel into forms, or in the form of pre-cast concrete planks or slabs, unless the 50 cubic yard limit is waived in writing by the district engineer;

(b) The boat ramp does not exceed 20 feet in width, unless this criterion is waived in writing by the district engineer;

(c) The base material is crushed stone, gravel or other suitable material;

(d) The excavation is limited to the area necessary for site preparation and all excavated material is removed to the upland; and,

(e) No material is placed in special aquatic sites, including wetlands.

The use of unsuitable material that is structurally unstable is not authorized. If dredging in navigable waters of the United States is necessary to provide access to the boat ramp, the dredging may be authorized by another NWP, a regional general permit, or an individual permit.

Notification: The permittee must submit a pre-construction notification to the district engineer prior to commencing the activity if: (1) The discharge into waters of the United States exceeds 50 cubic yards, or (2) the boat ramp exceeds 20 feet in width. (Sections 10 and 404)

US Army Corps of Engineers®
Nashville District

Nationwide Permit Conditions

The following General Conditions must be followed in order for any authorization by NWP to be valid:

1. Navigation. (a) No activity may cause more than a minimal adverse effect on navigation. (b) Any safety lights and signals prescribed by the US Coast Guard, through regulations or otherwise, must be installed and maintained at the permittee's expense on authorized facilities in navigable waters of the US. (c) The permittee understands and agrees that, if future operations by the US require the removal, relocation, or other alteration, of the structure or work herein authorized, or if, in the opinion of the Secretary of the Army or his authorized representative, said structure or work shall cause unreasonable obstruction to the free navigation of the navigable waters, the permittee will be required, upon due notice from the Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the US. No claim shall be made against the US on account of any such removal or alteration.

2. Aquatic Life Movements. No activity may substantially disrupt the necessary life cycle movements of those species of aquatic life indigenous to the waterbody, including those species that normally migrate through the area, unless the activity's primary purpose is to impound water. Culverts placed in streams must be installed to maintain low flow conditions.

3. Spawning Areas. Activities in spawning areas during spawning seasons must be avoided to the maximum extent practicable. Activities that result in the physical destruction (e.g., through excavation, fill, or downstream smothering by substantial turbidity) of an important spawning area are not authorized.

4. Migratory Bird Breeding Areas. Activities in waters of the US that serve as breeding areas for migratory birds must be avoided to the maximum extent practicable.

5. Shellfish Beds. No activity may occur in areas of concentrated shellfish populations, unless the activity is related to a shellfish harvesting activity authorized by NWP 4 and 48.

6. Suitable Material. No activity may use unsuitable material (e.g., trash, debris, car bodies, asphalt, etc.). Material used for construction or discharged must be free from toxic pollutants in toxic amounts (see Section 307 of the Clean Water Act).

7. Water Supply Intakes. No activity may occur in the proximity of a public water supply intake, except where the activity is for the repair or improvement of public water supply intake structures or adjacent bank stabilization.

8. Adverse Effects from Impoundments. If the activity creates an impoundment of water, adverse effects to the aquatic system due to accelerating the passage of water, and/or restricting its flow must be minimized to the maximum extent practicable.

9. Management of Water Flows. To the maximum extent practicable, the preconstruction course, condition, capacity, and location of open waters must be maintained for each activity, including stream channelization and storm water management activities, except as provided below. The activity must be constructed to withstand expected high flows. The activity must not restrict or impede the passage of normal or high flows, unless the primary purpose of the activity is to impound water or manage high flows. The activity may alter the preconstruction course; condition, capacity, and location of open waters if it benefits the aquatic environment (e.g. stream restoration or relocation activities).

10. Fills Within 100-Year Floodplains. The activity must comply with applicable FEMA-approved state or local floodplain management requirements.

11. Equipment. Heavy equipment working in wetlands or mudflats must be placed on mats, or other measures must be taken to minimize soil disturbance.

12. Soil Erosion and Sediment Controls. Appropriate soil erosion and sediment controls must be used and maintained in effective operating condition during construction, and all exposed soil and other fills, as well as any work below the ordinary high water mark or high tide line, must be permanently stabilized at the earliest practicable date. Permittees are encouraged to perform work within waters of the US during periods of low-flow or no-flow.

13. Removal of Temporary Fills. Temporary fills must be removed in their entirety and the affected areas returned to pre-construction elevations and revegetated, as appropriate.

14. Proper Maintenance. Any authorized structure or fill shall be properly maintained, including maintenance to ensure public safety.

15. Wild and Scenic Rivers. No activity may occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a "study river" for possible inclusion in the system while the river is in an official study status, unless the appropriate Federal agency with direct management responsibility for such river, has determined in writing that the proposed activity will not adversely affect the Wild and Scenic River designation or study status. Information on Wild and Scenic Rivers may be obtained from the appropriate Federal land management agency in the area (e.g., National Park Service, US Forest Service, US Fish and Wildlife Service).

16. Tribal Rights. No activity or its operation may impair reserved tribal rights, including, but not limited to, reserved water rights and treaty fishing and hunting rights.

17. Endangered Species. (a) No activity is authorized under any NWP which is likely to jeopardize the continued existence of a threatened or endangered species or a species proposed for such designation, as identified under the Federal Endangered Species Act (ESA), or which will destroy or adversely modify the critical habitat of such species. Non-

federal permittees shall notify the District Engineer if any listed species or designated critical habitat might be affected or is in the vicinity of the project, or is located in the designated critical habitat and shall not begin work on the activity until notified by the District Engineer that the requirements of the ESA have been satisfied and that the activity is authorized. For activities that may affect Federally-listed species or designated critical habitat, the notification must include the name(s) of the endangered or threatened species that may be affected by the proposed work or that utilize the designated critical habitat that may be affected by the proposed work. As a result of formal or informal consultation with the FWS, the District Engineer may add species-specific regional endangered species conditions to the NWP.

(b) Authorization of an activity by a NWP does not authorize the ``take" of a threatened or endangered species as defined under the ESA. In the absence of separate authorization (e.g., an ESA Section 10 Permit, a Biological Opinion with ``incidental take" provisions, etc.) from the USFWS or the NMFS, both lethal and non-lethal ``takes" of protected species are in violation of the ESA. Information on the location of threatened and endangered species and their critical habitat can be obtained directly from the offices of the USFWS and NMFS or their World Wide Webpages at http://www.fws.gov/ and http://www.noaa.gov/fisheries.htmlrespectively.

18. Historic Properties. No activity which may affect historic properties listed or eligible for listing, in the National Register of Historic Places is authorized, until the District Engineer has complied with the provisions of 33 CFR part 325, Appendix C. The prospective permittee must notify the District Engineer if the authorized activity may affect any historic properties listed, determined to be eligible, or which the prospective permittee has reason to believe may be eligible for listing on the National Register of Historic Places, and shall not begin the activity until notified by the District Engineer that the requirements of the National Historic Preservation Act have been satisfied and that the activity is authorized. Information on the location and existence of historic resources can be obtained from the State Historic Preservation Office Officer or Tribal Historic Preservation Officer, as appropriate, and the National Register of Historic Places (see 33 CFR 330.4(g)). For activities that may affect historic properties listed in, or eligible for listing in, the National Register of Historic Places, the notification must state which historic property may be affected by the proposed work or include a vicinity map indicating the location of the historic property. Prospective permittees should beware that section 110k of the NHPA (16 USC 470h–2(k)) prevents the Corps from granting a permit or other assistance to an applicant who, with intent to avoid the requirements of Section 106 of the NHPA, has intentionally significantly adversely affected a historic property to which the permit would relate, or having legal power to prevent it, allowed such significant adverse effect to occur.

19. Designated Critical Resource Waters. Critical resource waters including state natural heritage sites, and outstanding national resource waters or other waters officially designated by a state as having particular environmental or ecological significance and identified by the district engineer after notice and opportunity for public comment. The district engineer may also designate additional critical resource waters after notice and opportunity for comment. (a) Discharges of dredged or fill material into waters of the US are not authorized by NWP 7, 12, 14, 16, 17, 21, 29, 31, 35, 39, 40, 42, 43, 44, 49, and 50 for any activity within, or directly affecting, critical resource waters, including wetlands adjacent to such waters. (b) For NWP 3, 8, 10, 13, 15, 18, 19, 22, 23, 25, 27, 28, 30, 33, 34, 36, 37, and 38, notification is required in accordance with general condition 27, for any activity proposed in the designated critical resource waters including wetlands adjacent to those waters. The district engineer may authorize activities under these NWPs only after it is determined that the impacts to the critical resource waters will be no more than minimal.

20. Mitigation. The activity must be constructed to avoid and minimize adverse effects, both temporary and permanent, to waters of the US to the maximum extent practicable at the project site (i.e. on site). Mitigation in all its forms (avoiding, minimizing, rectifying, reducing, or compensating) will be required to the extent necessary to ensure that the adverse effects to the aquatic environment are minimal.

21. Water Quality Certification. The activity must comply with case specific conditions added by the Corps or by the state, Indian Tribe, or USEPA in its section 401 Water Quality Certification. Where States and authorized Tribes, or EPA where applicable, have not previously certified compliance of an NWP with CWA Section 401, individual 401 Water Quality Certification must be obtained or waived (see 33 CFR 330.4(c)). The district engineer or State or Tribe may require additional water quality management measures to ensure that the authorized activity does not result in more than minimal degradation of water quality.

22. Use of Multiple Nationwide Permits. The use of more than one NWP for a single and complete project is prohibited, except when the acreage loss of waters of the US authorized by the NWPs does not exceed the acreage limit of the NWP with the highest specified acreage limit. For example, if a road crossing over tidal water is constructed under NWP14, with associated bank stabilization authorized by NWP 13, the maximum acreage loss of waters of the US for the total project cannot exceed 1⁄3-acre.

23. Transfer of Nationwide Permit Verifications. If the permittee sells the property associated with NWP verification, the permittee may transfer the NWP verification to the new owner by submitting a letter to the appropriate Corps district office to validate the transfer. A copy of the NWP verification must be attached to the letter, and the letter must contain the following statement: When the structures or work authorized by this NWP are still in existence at the time the property is transferred, the terms and conditions of this NWP, including any special conditions, will continue to be binding on the new owner(s) of the property. To validate the transfer and the associated liabilities associated with compliance with its terms and conditions, have the transferee sign and date below:

_____ _____

Transferee Date

24. Compliance Certification. Every permittee who has received a Nationwide permit verification from the Corps will submit a signed certification regarding the completed work and any required mitigation. The certification form is included with this verification.

25. Single and Complete Project. The activity must be a single and complete project. The same NWP cannot be used more than once for the same single and complete project.

Further Information:

1. District Engineers have authority to determine if an activity complies with the terms and conditions of an NWP.
2. NWPs do not obviate the need to obtain other Federal, state, or local permits, approvals, or authorizations required by law.
3. NWPs do not grant any property rights or exclusive privileges.
4. NWPs do not authorize any injury to the property or rights of others.
5. NWPs do not authorize interference with any existing or proposed Federal project.

STATE OF TENNESSEE

NPDES PERMIT

Tracking No. TNR132647

NOTICE OF COVERAGE UNDER THE GENERAL NPDES PERMIT FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY (CGP)

Tennessee Department of Environment and Conservation
Division of Water Pollution Control
401 Church Street, 6th Floor, L&C Annex
Nashville, Tennessee 37243-1534

Under authority of the Tennessee Water Quality Control Act of 1977 (T.C.A. 69-3-101 et seq.) and the delegation of authority from the United States Environmental Protection Agency under the Federal Water Pollution Control Act, as amended by the Clean Water Act of 1977 (33 U.S.C. 1251, et seq.):

Name of the Construction Project:	**Jefferson Park Subdivision (96 acres)**
Construction site Owner/Developer:	**Mesana Investments, LLC**
Contractor(s):	**no contractor**
is authorized to discharge:	storm water associated with construction activity
from site located at:	**South Northshore Drive, Knox County**
to receiving waters named:	**Little Turkey Creek**

in accordance with effluent limitations, monitoring requirements and other conditions set forth herein.

Likely presence of threatened or endangered species in one mile radius: **NO**
Likely presence of threatened or endangered species downstream: **NO**

Additional pollution prevention requirements apply for discharges into waters which TDEC identifies as:
a) impaired by siltation: **YES** b) high quality waters: **NO**

Your coverage under the CGP shall become effective on **July 13, 2007**, and shall be terminated upon receipt of Notice of Termination, or the date of expiration of the CGP, **May 30, 2010**.

Paul E. Davis

Paul E. Davis, Director
Division of Water Pollution Control

CN-0759

RDAs 2352 and 2366

General Permit for Bank Stabilization

Effective Date: July 1, 2005
Expiration Date: June 30, 2010

This general permit authorizes the repair and protection of eroded stream and reservoir banks. Bank stabilization activities typically include grading of the bank to the appropriate slope, based on hydrology, in conjunction with the placement of riprap, gabion baskets and/or installation of bioengineering techniques. Bioengineering techniques shall incorporate primarily materials found in the natural riparian environment, such as cedar tree revetments, rock or log current deflection weirs, live willow post application and log crib structures.

Failure to comply with the terms and conditions of this permit is a violation of the *Tennessee Water Quality Control Act of 1977* and is subject to penalty in accordance with T.C.A. §69-3-115.

Exclusions

This general permit shall not be used to authorize activities in the following circumstances:

1) where the proposed activity may adversely affect wetlands;
2) where a portion of the proposed activity is located in any waterway which is identified by the department as having contaminated sediments, and where the activity will likely mobilize the contaminated sediments;
3) when the proposed activity will adversely affect a species formally listed on either state or federal lists of threatened or endangered species or their critical habitat;
4) when the department determines that the proposed activities, either individually or cumulatively, may result in degradation to waters of the state; or
5) when an individual permit is otherwise required.

Projects not qualifying for authorization under this general permit, may be authorized by an individual permit, provided that all requirements of the *Tennessee Water Quality Control Act of 1977* are met.

Notification

1) Notification to the division is **not** required where:
   (a) the length of the stream or reservoir bank to be treated is less than three times the top-of-bank width of the stream channel, not to exceed a total length of 50 feet, and where the total volume of soil, sand or gravel disturbed or re-deposited is less than ten cubic yards. Bank stabilization work conducted in accordance with this provision is limited to one site per 1000 linear feet of stream or reservoir bank, and may be done only once without notification; or
   (b) the activity is located within water resource development lands and waters, including flowage easement, managed by the Tennessee Valley Authority (TVA) or the United States Army Corps of Engineers (USCOE)
2) Except as provided in item 1) of this section, notification to the division is required by submission of an original, signed application (form CN-1091) along with the following minimum information:
   (a) a cover letter explaining the scope of the project;
   (b) a USGS topographical map showing the exact location of the proposed project; and
   (c) a single copy of construction plans and drawings which include all dimensions and specifications for the proposed work, as well as pollution control methods and/or structures.

Except as provided in item 1) of this section, work shall not commence until the applicant has received written authorization from the division that the proposed activities may proceed under this general permit or that an individual permit has been issued.

All activities covered under this general permit, with or without notification, shall comply with all terms and conditions contained hereinafter.

Terms and Conditions

1) The work shall be accomplished in conformance with the accepted plans, specifications, data and other information submitted in support of the above mentioned application and the limitations, requirements, and conditions set forth herein.
2) Applicant is responsible for obtaining the necessary authorization pursuant to applicable provisions of §10 of *The Rivers and Harbors Act of 1899*; §404 of *The Clean Water Act* and §26a of *The Tennessee Valley Authority Act*, as well as any other federal, state or local laws.
3) Applicant is responsible for obtaining coverage under the National Pollutant Discharge Elimination System (NPDES) General Permit for Storm Water Discharges from Construction Activities for construction sites involving clearing, grading or excavation that result in an area of disturbance of one or more acres, and activities that result in the disturbance of less than one acre if it is part of a larger common plan of development or sale.
4) Where the activity is **not** located within water resource development lands and waters, including flowage easement, managed by the TVA or the USCOE, the placement of riprap is limited to 300 linear feet of stream or reservoir bank. Vegetative or bioengineering methods of bank stabilization and activities located within water resource development lands and waters, including flowage easement, managed by the TVA or the USCOE are not subject to this restriction.
5) Sediment shall be prevented from entering waters of the state. Erosion and sediment controls shall be designed according to the size and slope of disturbed or drainage areas to detain runoff and trap sediment and shall be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices.
6) Erosion and sediment control measures shall be in place and functional before earth moving operations begin, and shall be constructed and maintained throughout the construction period. Temporary measures may be removed at the beginning of the work day, but shall be replaced at the end of the work day.
7) Sediment should be removed from sediment traps, silt fences, sedimentation ponds, and other sediment controls as necessary, and shall be removed when design capacity has been reduced by 50%. Discharges from sediment basins and traps shall be through a pipe or lined or well-grassed channel so that the discharge does not cause erosion.
8) Litter, construction debris, and construction chemicals exposed to storm water shall be picked up prior to anticipated storm events (e.g. forecasted by local weather reports), or otherwise prevented from becoming a pollutant source for storm water discharges (e.g., screening outfalls, daily pick-up, etc.). After use, silt fences should be removed or otherwise prevented from becoming a pollutant source for storm water discharges.
9) Clearing, grubbing and other disturbance to the riparian vegetation shall be kept at the minimum necessary for slope construction and equipment operations. Unnecessary riparian vegetation removal, including trees, is prohibited.
10) Pre-construction vegetative ground cover shall not be destroyed, removed or disturbed more than 10 calendar days prior to grading or earth moving unless the area is seeded and/or mulched or other temporary cover is installed.
11) Excavated materials, removed vegetation, construction debris, and other wastes shall be removed to an upland location and properly stabilized or disposed of in such a manner as to prevent reentry into the waterway.
12) Stabilization measures shall be initiated within seven days after the construction activity has temporarily or permanently ceased.
13) Temporary or permanent soil stabilization shall be accomplished within 15 days after final grading or other earth work. Permanent stabilization with perennial vegetation (using native herbaceous and woody plants where practicable) or other permanently stable, non-eroding surface shall replace any temporary measures as soon as practicable.
14) Muddy water to be pumped from excavation and work areas shall be held in settling basins or filtered prior to its discharge into surface waters. Settling basins shall not be located closer than 20 feet from the top bank of the stream and water shall be discharged through a pipe, well grassed or lined channel or other equivalent means so that the discharge does not cause erosion and sedimentation.
15) The activity may not be conducted in a manner that would permanently disrupt the movement of fish and aquatic life.

16) Stream beds shall not be used as transportation routes for construction equipment. Temporary stream crossings shall be limited to one point in the construction area and erosion control measures shall be utilized where stream banks are disturbed. Stream crossings should be constructed of clean rock and stream flow should be conveyed in appropriately sized pipe. The crossing shall be constructed so that stream flow is not obstructed. Following construction, all materials used for the temporary crossing shall be removed and disturbed stream banks shall be restored and stabilized if needed.
17) Materials used in bank stabilization shall include clean rock, riprap, anchored trees or other non-erodible materials found in the natural environment. Except for activities covered by item 1)(a) of the Notification section, stabilization materials shall not include gravel, sand, sediments, chert, soil or other materials that are likely to erode.
18) Materials used in bank stabilization projects shall be free of contaminants, including toxic pollutants, hazardous substances, waste metal, construction debris and other wastes as defined by T.C.A. 69-3-103(18).
19) Material may not be placed in a location or manner so as to impair surface water flow into or out of any wetland area.
20) Appropriate steps shall be taken to ensure that petroleum products or other chemical pollutants are prevented from entering waters of the state. All spills shall be reported to the appropriate emergency management agency and to the division. In the event of a spill, measures shall be taken immediately to prevent pollution of waters of the state, including groundwater.
21) This general permit does not authorize impacts to cultural, historical or archaeological features or sites.
22) Where authorization is required, the division will establish an expiration date for coverage under this general permit that is specific to the authorization and separate from the general permit expiration date.

APPROVED: Paul E. Davis

Paul E. Davis, Director, Water Pollution Control

DATE: 6-30-05

General Permit for Construction of Launching Ramps and Public Access Structures

Effective Date: July 1, 2005
Expiration Date: June 30, 2010

This general permit authorizes the construction of boat launching ramps and public access structures in waters of the state. Public access structures include, but are not limited to, fishing piers, handicap access ramps and greenway trails.

Failure to comply with the terms and conditions of this permit is a violation of the *Tennessee Water Quality Control Act of 1977* and is subject to penalty in accordance with T.C.A. §69-3-115.

Exclusions

This general permit shall not be used to authorize activities in the following circumstances:

1) where the proposed activity may adversely affect wetlands;
2) where a portion of the proposed activity is located in a component of the National Wild and Scenic River System, a State Scenic River, waters designated as Outstanding National Resource Waters;
3) where a portion of the proposed activity is located in any waterway which is identified by the department as having contaminated sediments, where the activity will likely mobilize the contaminated sediments;
4) when the proposed activity will adversely affect a species formally listed on either state or federal lists of threatened or endangered species or their critical habitat;
5) when the department determines that the proposed activities, either individually or cumulatively, may result in degradation to waters of the state; or
6) when an individual permit is otherwise required.

Projects not qualifying for authorization under this general permit, may be authorized by an individual permit, provided that all requirements of the *Tennessee Water Quality Control Act of 1977* are met.

Notification

1) Notification to the division is **not** required where the activity is located within water resource development lands and waters, including flowage easement, managed by the Tennessee Valley Authority (TVA) or the United States Army Corps of Engineers (USCOE).
2) Except as provided in item 1) of this section, notification to the division is required by submission of an original, signed application (form CN-1091) along with the following minimum information:
   (a) a cover letter explaining the scope of the project;
   (b) a USGS topographical map showing the exact location of the proposed project; and
   (c) a single copy of construction plans and drawings which include all dimensions and specifications for the proposed work, as well as pollution control methods and/or structures.

Except as provided in item 1) of this section, work shall not commence until the applicant has received written authorization from the division that the proposed activities may proceed under this general permit or that an individual permit has been issued.

All activities covered under this general permit, with or without notification, shall comply with all terms and conditions contained hereinafter.

Terms and Conditions

1) The work shall be accomplished in conformance with the accepted plans, specifications, data and other information submitted in support of the above mentioned application and the limitations, requirements, and conditions set forth herein.
2) Applicant is responsible for obtaining the necessary authorization pursuant to applicable provisions of §10 of *The Rivers and Harbors Act of 1899*; §404 of *The Clean Water Act* and §26a of *The Tennessee Valley Authority Act*, as well as any other federal, state or local laws.

3) Applicant is responsible for obtaining coverage under the National Pollutant Discharge Elimination System (NPDES) General Permit for Storm Water Discharges from Construction Activities for construction sites involving clearing, grading or excavation that result in an area of disturbance of one or more acres, and activities that result in the disturbance of less than one acre if it is part of a larger common plan of development or sale.
4) For proposed projects that are **not** located within water resource development lands and waters, including flowage easement, managed by the TVA or the USCOE, the total width including base fill material, **may not exceed 20 feet**.
5) Ramps constructed on fill material shall have the side slopes stabilized with riprap.
6) The ramp or public access structures shall be constructed in the dry to the maximum extent practicable during winter drawdown periods of lakes/reservoirs or during low flow periods of free flowing streams.
7) Sediment shall be prevented from entering waters of the state. Erosion and sediment controls shall be designed according to the size and slope of disturbed or drainage areas to detain runoff and trap sediment and shall be properly selected, installed, and maintained in accordance with the manufacturer's specifications and good engineering practices.
8) Erosion and sediment control measures shall be in place and functional before earth moving operations begin, and shall be constructed and maintained throughout the construction period. Temporary measures may be removed at the beginning of the work day, but shall be replaced at the end of the work day.
9) Sediment should be removed from sediment traps, silt fences, sedimentation ponds, and other sediment controls as necessary, and shall be removed when design capacity has been reduced by 50%. Discharges from sediment basins and traps shall be through a pipe or lined or well-grassed channel so that the discharge does not cause erosion.
10) Litter, construction debris, and construction chemicals exposed to storm water shall be picked up prior to anticipated storm events (e.g. forecasted by local weather reports), or otherwise prevented from becoming a pollutant source for storm water discharges (e.g., screening outfalls, daily pick-up, etc.). After use, silt fences should be removed or otherwise prevented from becoming a pollutant source for storm water discharges.
11) Clearing, grubbing and other disturbance to the riparian vegetation shall be kept at the minimum necessary for slope construction and equipment operations. Unnecessary riparian vegetation removal, including trees, is prohibited.
12) Pre-construction vegetative ground cover shall not be destroyed, removed or disturbed more than 10 calendar days prior to grading or earth moving unless the area is seeded and/or mulched or other temporary cover is installed.
13) Stabilization measures shall be initiated within seven days after the construction activity has temporarily or permanently ceased.
14) Temporary or permanent soil stabilization shall be accomplished within 15 days after final grading or other earth work. Permanent stabilization with perennial vegetation (using native herbaceous and woody plants where practicable) or other permanently stable, non-eroding surface shall replace any temporary measures as soon as practicable.
15) Muddy water to be pumped from excavation and work areas shall be held in settling basins or filtered prior to its discharge into surface waters. Settling basins shall not be located closer than 20 feet from the top bank of the stream and water shall be discharged through a pipe, well grassed or lined channel or other equivalent means so that the discharge does not cause erosion and sedimentation.
16) Material may not be placed in a location or manner so as to impair surface water flow into or out of any wetland area.
17) Excavated materials, removed vegetation, construction debris, and other wastes shall be removed to an upland location and properly stabilized or disposed of in such a manner as to prevent reentry into the waterway.
18) Materials used in construction of boat launching ramps and public access structures shall be free of contaminants, including toxic pollutants, hazardous substances, waste metal, construction debris and other wastes as defined by T.C.A. 69-3-103(18).
19) Appropriate steps shall be taken to ensure that petroleum products or other chemical pollutants are prevented from entering waters of the state. All spills shall be reported to the appropriate emergency management agency and to the division. In the event of a spill, measures shall be taken immediately to prevent pollution of waters of the state, including groundwater.

20) This general permit does not authorize impacts to cultural, historical or archaeological features or sites.
21) Where authorization is required, the division will establish an expiration date for coverage under this general permit that is specific to the authorization and separate from the general permit expiration date.

APPROVED: Paul E. Davis

Paul E. Davis, Director, Water Pollution Control

DATE: 6-30-05

Page intentionally blank